



TEST REPORT	PRODUCT:	7744 •
FCA MS-CC-240 [2019-06-19] Change H	TEST SUBSTRATE:	TFPP, TPO and ABS
DOCUMENT TITLE: Adhesive – Pressure Sensitive – Transfer Film	REPORT DATE:	06/26/23

Table 2 – Peel Tests (At 90 Degrees and 51mm [2 in] Per Minute)

	REQUIREMENT		RESULTS	
	<u>N/mm</u>	<u>TFPP</u>	<u>TPO</u> +	<u>ABS</u>
INITIAL (20 MINUTES)	0.44 N/mm	0.63 N/mm	0.73 N/mm	0.81 N/mm
INITIAL (24 HOURS)	0.53 N/mm	0.86 N/mm	0.54 N/mm	1.01 N/mm
AFTER 50 HOURS @ 79°C	0.88 N/mm	1.13 N/mm	0.97 N/mm	1.38 N/mm
AFTER 100 HOURS RELATIVE HUMIDY @ 38°C ② ◆	0.70 N/mm	0.76 N/mm	0.78 N/mm	1.05 N/mm
AFTER 3 CYCLES (1 Cycle is 24h 79°C, 24h 100% RH @ 38°C, 24h -29°C) ③ ◆	0.70 N/mm	1.13 N/mm	1.07 N/mm	1.59 N/mm

⁺ Solvay Sequel 1402

- Adchem product tested applied to 0.002" Polycarbonate overlay material.
- EXCEPTION: Utilized standard humidity at 97% RH in place of Water Fog per ASTM D 1735
- EXCEPTION: Utilized standard humidity at 97% RH in place of 100% RH humidity specified

♦ Results for this test are Non-Accredited Data due to Exception as stated

APPROVED:

Original Test Date: 4/26/21

Berry Global Technical Service Department

Results in RED did not meet stated requirement